

INDUSTRIAL DEVELOPMENT DEMOLITION & REMEDIATION

ICA Property

Villawood, N.S.W.



The project scope involved the removal of 18,000m² of asbestos-cement sheeting, along with 16,000m³ of bulk excavation and filling works.

The excavation area had been contaminated as a result of leaking underground petroleum storage tanks, with a large portion of the material requiring treatment. The contaminated fill was successfully land farmed on site, and subsequently used as fill under the new pavement areas.